

Manufacturer`s Declaration of Conformity

Hirschmann Automation and Control GmbH

**Stuttgarter Straße 45-51
D-72654 Neckartenzlingen, Germany**

declares in sole responsibility, that the product(s)

Unmanaged Rail Switch

(Product description)

**SPR20-8TX-EEC, 942 335-017,
SPR40-8TX-EEC, 942 335-020,
SPR20-8TX/1FM-EEC, 942 335-028,
SPR20-7TX/2FM-EEC, 942 335-030,
SPR20-7TX/2FS-EEC, 942 335-031,
SPR40-1TX/1SFP-EEC, 942 335-033,
SPR40-1TX/1SFP-EEC-HO, 942 335-501**

optional assembled with the transceivers: M-Fast SFP-x, M-SFP-x, SFP-FAST-x and SFP-GIG-x.
(x = any suffix)

(Type, reference number)

has been designed and manufactured in accordance with the following standards

IEC/EN 61850-3:2014 – Communication networks and systems in substations

Test description	IEC 61850-3 Section	Test Reference	Requirement
Dry heat test operational	6.9.3.1	IEC 60068-2-2	+70 °C
Cold test operational	6.9.3.2	IEC 60068-2-1	-40 °C
Dry heat test storage	6.9.3.3	IEC 60068-2-2	+85 °C
Cold test storage	6.9.3.4	IEC 60068-2-1	-40 °C
Change of temperature test, operational	6.9.3.5	IEC 60068-2-14	-40 °C / 70 °C
Damp heat cyclic test	6.9.3.7	IEC 60068-2-30	Test Db, 95 % (6 x 24h cycles)


Test description	IEC 61850-3 Section	Test Reference	Requirement
Vibration response and endurance (sinusoidal)	6.10.1	IEC 60255-21-1	Class 1 response: 10-59 Hz: 0,035 mm, 59-150 Hz: 0,5 g endurance: 59-150 Hz: 1,0 g
Shock response and shock withstand (half sine)	6.10.2	IEC 60255-21-2	Class 1 response: 5 g, 11 ms endurance: 15 g, 11 ms
Bumps	6.10.2	IEC 60255-21-2	Class 0
Seismic	6.10.3	IEC 60255-21-3	Class 1 1-8,5 Hz: 3,5 mm (x) / 1,5 mm (y) 8,5-35 Hz: 1 g (x) / 0,5 g (y)
IP protection class	6.11	IEC 60529	IP 40
Rated voltage, operating range	5.2		<i>DC power ports:</i> Urated: 12-24 V, -20 % to +10 %
Product safety requirements	6.6.3	Impulse voltage	±5 kV
	6.6.4	Dielectric voltage test	0,7 kV d.c.
	6.6.5	Protective bonding resistance	0,1 Ω
Electrostatic discharge	6.7.3	Table 9.3 (Basic: IEC 61000-4-2)	Level 3, 6 kV contact / 8 kV air
Radiated electromagnetic field	6.7.3	Table 9.2 (Basic: IEC 61000-4-3)	Level 3, 10 V/m 80 – 3000 MHz
Fast transient / burst	6.7.3	Table 10.4, 11.5, 12.7 (Basic: IEC 61000-4-4)	<i>Signal ports, power ports:</i> CM Level 4, ±4 kV
Surges 1,2/50µs	6.7.3	Table 10.2, 11.3, 12.5 (Basic: IEC 61000-4-5)	<i>Signal ports :</i> CM Level 4, ±4 kV <i>DC-power ports:</i> CM Level 3, ±2 kV DM Level 2, ±1 kV


Test description	IEC 61850-3 Section	Test Reference	Requirement
Conducted disturbances by RF fields	6.7.3	Table 10.5, 11.6, 12.8, 13.2 (Basic: IEC 61000-4-6)	Level 3, 10 V 150 kHz – 80 MHz
Damped oscillatory wave 1MHz	6.7.3	Table 10.3, 11.4, 12.6 (Basic: IEC 61000-4-18)	<i>Signal ports, power ports:</i> CM Level 3, 2,5 kV DM Level 3, 1,0 kV
Main frequency voltage	6.7.3	Table 10.1, 12.4 (Basic: IEC 61000-4-16)	<i>Signal ports, DC power ports:</i> Level 4, 30 V cont., 300 V 1s
Voltage dips	6.7.3	Table 12.1 (Basic: IEC 61000-4-29)	<i>DC Power Ports</i> ΔU 30% for 0,1 s ΔU 60% for 0,1 s *2)
Voltage interruptions	6.7.3	Table 12.2 (Basic: IEC 61000-4-29)	<i>DC Power Ports</i> ΔU 100% for 0,05 s *2)
Ripple on DC power supply	6.7.3	Table 12.3 (Basic: IEC 61000-4-17)	10 %
Radiated Emission	6.7.4	Table 16.1, 17.1 CISPR22	30...230 MHz: 40 dB μ V/m (10m) 230...1000 MHz: 47 dB μ V/m (10m) 1...3 GHz: 56 dB(μ V)/m av. 76 dB(μ V)/m pk. (3m) 3...6 GHz: 60 dB(μ V)/m av. 80 dB(μ V)/m pk. (3m)
Conducted Emission	6.7.4	Table 14.1, 15.1 CISPR22	<i>Power ports:</i> 150...500 kHz: 79 dB μ V qp. 66 dB μ V av. 500 kHz...30 MHz: 73 dB μ V qp. 60 dB μ V av. <i>Telecommunication ports:</i> 150...500 kHz: 97 to 87 dB μ V qp. 84 to 74 dB μ V av. 500 kHz...30 MHz: 87 dB μ V qp. 74 dB μ V av.

*2) For continuous operation according to 7.5.2c, a redundant power source or an UPS is recommended.

IEEE 1613:2009 – Devices in Electrical Power Substations

Test description	IEEE 1613 Section	Test Reference	Requirement
Operational temperature range	3.1.1	-	-40 °C to +70 °C
Nonoperational temperature range	3.1.2	-	-40 °C to +85 °C
Relative humidity communication equipment	3.1.3	-	95 %, 96 hours
DC rated control power inputs	4.1	-	24 V rated, 32 V max.
AC component in DC control voltage supply	4.2	-	5% peak
Dielectric test	5.2	-	U _{rated} ≤ 48 V; 0,7 kV DC
Impulse voltage test	5.3	-	±5 kV
Oscillatory wave test 1MHz	6	-	2,5 kV CM 2,5 kV DM
Fast transient / burst	6	-	±4 kV CM
Radiated electromagnetic field	7	-	20 V/m rms (35 V/m peak) 80 – 1000 MHz
Electrostatic Discharge	8	-	±8 kV contact discharge ±15 kV air discharge
Vibration	9	-	Class V.S.2 10 mm/s, 1-150 Hz
Device cooling	10	-	Convection cooled without fans


 (Wolfgang Schenk
 VP Business Development
 Industrial Automation)


 (i.V. Peter Schumacher
 Quality Manager)

Neckartenzlingen, 2023-11-14
 (Issue place and date)